



**ST. CLAIR CATHOLIC  
DISTRICT SCHOOL BOARD**

*Lighting the Way ~ Rejoicing in Our Journey*

**REQUEST FOR TENDER  
FOR  
ROOF MAINTENANCE PROGRAM  
CHATHAM-KENT CATHOLIC SCHOOLS**

**RFT #: CP1617**

**ADDENDUM #1  
QUESTIONS & ANSWERS**

**DUE DATE: June 14, 2016 at 4:00:00p.m., Local Time**

**Mailing Address:**  
Mr. Tony Prizio  
Purchasing Department  
St. Clair Catholic District School Board  
420 Creek Street  
Wallaceburg, ON  
N8A 4C4

**ADDENDUM, QUESTIONS & ANSWERS**

## ADDENDUM #1

A1. Reply to questions received.

## QUESTIONS AND ANSWERS

### 1. St. Vincent Catholic School

Roof Area 'C' (Item № 3)

Currently there is no support on one of the standing seam panels adjacent to Roof Area 'D', therefore additional support (1½" x 1½" x 3/16" angle) is required to be installed underneath for support to above deflection of the panel above once weight is applied. (ACCESS WILL HAVE TO BE GIVEN TO COMPLETE THIS REPAIR)

### 2. St. Joseph Catholic School

Roof Area 'D' (Item № 10)

This item clearly indicates a new outlet connector is required to be installed in the scupper drain in order to connect to the current downpipe to avoid water running outside the downpipe and along the exterior façade of building.

### 3. All Schools with EPDM Repairs

Firestone Membrane Manufacturer would be acceptable providing that all materials in question meet or exceed the specified repair procedures.

### 4. Would Extruded Polystyrene Pavers Supports be a suitable alternative to cut and painted rigid board?

Tender to be priced as specified.

### 5. When pricing each roof section at each school. Are we price each section individually?

Yes- Itemized as requested in document

6. I know that the tender form shows them as individually areas, but if are "A" only requires a part sheet or roll. Can the remainder of the material be applied to another area?

Yes

This concludes the addendum #1.